

## HOMEOWNER QMP MINIMUM REQUIREMENTS SITE BUILT NEW SINGLE FAMILY RESIDENTIAL PERMIT INSPECTION STAGES

ALLOW 2 to 5 BUSINESS DAYS NOTICE WHEN CALLING FOR AN INSPECTION Online inspection request is available at www.inspectionsgroup.com

## NOTE: the applicant may request additional inspections for an additional fee

BUILDING PERMITS	
Foundation prior to backfill:	<ul> <li>Footings and walls poured with forms removed</li> </ul>
	Weeping tile in place
	<ul> <li>Washed rock and damp proofing in place</li> </ul>
Framing prior to drywall:	<ul> <li>Framing of walls, floors and roof complete prior to insulation</li> </ul>
	Building accessible for inspection
	<ul> <li>Manufactured engineered floor joist layouts on site</li> </ul>
	<ul> <li>Truss layout and roof bracing details on site</li> </ul>
Final prior to occupancy within 365 days of permit issuance:	Handrails in place and guards complete
	<ul> <li>Heating/ventilation system installed and ductwork complete</li> </ul>
	<ul> <li>Smoke alarms and carbon monoxide detectors installed</li> </ul>
	All items from previous inspection reports or plan examination complete
ELECTRICAL PERMITS	
Rough in prior to drywall:	Main service installed
	All wire and boxes installed and visible
	Bonding and grounding complete
Final prior to occupancy within 365 days of permit issuance:	All items from previous inspection reports complete
	Panel labeled
	Smoke alarms installed
	<ul> <li>All load devices and switches installed and operational</li> </ul>
GAS PERMITS	
Final prior to occupancy within 365 days of permit issuance:	All gas piping installed
	Pressure test complete
	Gas meter installed
	All fixtures installed, vented and operational
PLUMBING PERMITS	
Rough in prior to covering:	All drain or sewer lines installed
	All water lines installed
	All vent stacks installed
Final prior to occupancy within	All items from previous inspection reports complete
365 days of permit issuance:	All fixtures installed and operational
PRIVATE SEWAGE DIS	POSAL SYSTEM PERMITS
Rough in prior to covering:	Majority of system installed with a portion left open for inspection

## The Inspections Group Inc.